

①.

Name = Asfandyas Anwar

ID = 7274

Subject = Structure I

Assignment = 04

②

DATE: \_\_\_\_\_

# cables and Arches

Q1

Sol

Member BC

---

$$\sum F_x = 0$$

$$-B_x = 0$$

Member AB

→ +

$$\sum F_x = 0$$

$$A_x = 0$$

Moment At A

$$\sum M_A = 0 \quad FH(4) - By(15) - 45(4.5) = 0$$

FBD

$$\sum M_C = 0 - FH(10) - by(30) + (45)$$

$$(30) = 0$$

$$FH = 153.4 \quad by = 0$$



(3)

DATE: \_\_\_\_\_

$$w_0 = \frac{2 F_y h}{12} = \frac{2 (153.4) (10)}{30}$$

$$= \frac{3068}{900} = 3.40$$

$$w_0 = 3.40 \text{ k/ft}$$

$$F_{\text{Max}} = w_0 L \sqrt{1 + \left(\frac{L}{24}\right)^2}$$

$$= 3.4 (30) \sqrt{1 + \left(\frac{30}{2(10)}\right)^2}$$

$$F_{\text{Max}} = 183.6 \text{ k}$$

Each hanger carries sft of car

$$T = (5 \text{ ft}) (3.4 \text{ k/ft})$$

$$T = 17 \text{ k}$$




AMMAR PAPER PRODUCTS

(4)

Q2

Sol:



Entire arch:

$$\sum M_a = 0 \quad -4(6) - 3(2) - 5(30) + C_y(40) = 0$$

$$C_y(40) = 165 \quad C_y = 4.125 \text{ K}$$

$$\sum F_x = 0 \quad A_x = 0$$

Sec BC:



(5)

DATE: \_\_\_\_\_

$$C_3 + \Sigma MB = 0$$

$$-5(10) - T(15) + 0.25(20) = 0$$

$$T = 3.67 \text{ k}$$



AMMAR PAPER PRODUCTS